

PROJECT FACT SHEET

CSA LATERAL DEVELOPMENT



SCOPE

- Mine development and ground support including load & haul of development waste to stope fill areas.
- Loading of development ore into client trucks as required.
- Intensive ground support regimes (up to 4 passes)

KEY PROJECT OUTCOMES

- Currently 2 year LTI free
- Achieving development metres in extremely hot environment as per clients expectations
- Rapid mobilisation and induction of personnel and equipment to site within 6 weeks

CSA Lateral Development, Cobar, NSW
Project Value: \$113M | Project Term: 36 months | Employees: 84

PROJECT STATISTICS

- Targeting 400m/month development

CONTRACT TYPE

- Schedule of Rates

KEY PLANT & EQUIPMENT

- 1 x Jumbo Sandvik - DD420-60C
- 1 x Jumbo Sandvik - DD421-60C
- 1 x Cabolter Sandvik - DS421C
- 2 x Loaders - Cat R2900G
- 2 x Trucks - Cat AD45B
- 1 x Charge up - Normet Charmec 1610B
- 2 x Integrated tool carriers - Volvo L60E
- 10 x Light vehicles
- 1 x Service truck

KEY MILESTONES

- Project commencement March 2012
- 7500m of development project to date

