

PROJECT FACT SHEET



NARRABRI DRIFT



SCOPE

Mine development utilising specialised drill and blast techniques through a basalt sill of the Narrabri North Coal Operation.

Installation of ground support and extraction of sill material to underground muck sumps and surface waste areas.

Installation & maintenance of ventilation, air, water & power reticulation. Shotcreting

KEY PROJECT OUTCOMES

- The project was a first for the NSW Coal Industry.
- Multi-faceted project required extensive scheduling & co-ordination to keep it on track and to budget
- PYBAR was able to showcase its capability in an extensive range of site operations in a new environment (coal)

LD Operations Ltd, Narrabri NSW
Project value \$ 8M | Project term: 6 months | Employees: 21

PRODUCTION STATISTICS

1.2 km's of development incorporating 3 drifts (1:8), 6m wide by 3.5m height

CONTRACT TYPE

Schedule of rates

KEY MILESTONES

- Commenced June 2009
- Completed November 2009

KEY PLANT & EQUIPMENT

2 x Tamrock Axera 7 –260 Jumbos

2 x Toro 1400 Loaders

2 x Toyota Hilux Duel Cab 4x4

2 x Toyota Landcruiser Troopy