

PROJECT FACT SHEET

BURBANKS



SCOPE

- Supply labour and plant, to re-establish the existing underground mine workings, including mine upgrades to emergency escape ways, dewatering, ventilation; and
- The mine exists through open pit, there are two ore bodies to be mined; Dahmu and Hadfeld; Dahmu being the main body via narrow vein mining techniques both mechanised and hand held development, traditional air leg rising and stoping methods.

KEY PROJECT OUTCOMES

- No MTI or LTIs; and
- Project mobilised within four weeks.

9km South East of Coolgardie, WA
Project Term: 15 months | Employees: 33

PROJECT STATISTICS

- Project completed.

CONTRACT TYPE

- Fixed and Variable charges for labour – where materials supplied at cost margin.

KEY PLANT & EQUIPMENT

- 1 x Jumbo – Tamrock Axera 5 single boom development jumbo;
- 1 x Loader – Cat R1300;
- 1 x Loader – LH203 (Tele-Remote);
- 1 x Truck – Cat AD45B Ejector;
- 1 x Longhole rig – Sandvik Solo 5-5V; and
- 8 x Rockdrills and Airlegs.

KEY MILESTONES

- Commencement date on site 2 May 2016.; and
- Project completed.