

PROJECT FACT SHEET

LADY LORETTA



SCOPE

- A greenfields infrastructure project ranging from portal establishment to point of readiness for mine production

KEY PROJECT OUTCOMES

- Project delivered 2 months ahead of schedule at below budget project costs for client
- Average 252m/mth development advance achieved versus 214m/mth scheduled
- Second jumbo scheduled for mid-project not required as schedule satisfied with one jumbo

Lady Loretta, QLD

Project Value: \$46 m | Project Term: 24 months | Employees: 50

PROJECT STATISTICS

- 6kms of development including stockpiles, cross cuts to the ore body, vent drives and diamond drill bays

CONTRACT TYPE

- Fixed and variable

KEY PLANT & EQUIPMENT

- 1 x Jumbo - Sandvik DD420
- 1 x Loader - Cat R2900
- 1 x Truck - Cat AD45B
- 1 x IT - Volvo L120
- 1 x Chargeup - Normet 1610B
- 1 x Agitator truck
- 1 x Shotcrete rig – Jaco Maxijet
- Site bus & LV's

KEY MILESTONES

- Project commencement: September 2011
- Second jumbo scheduled October 2012
- Scheduled completion: September 2013
- Actual completion: early August 2013

Monthly jumbo performance

