

# PROJECT FACT SHEET

## CARRAPATEENA



### SCOPE

- Early Works Program - 7.5km of initial decline development; and
- Revision to mine design now twin decline access to orebody.

### KEY PROJECT OUTCOMES

- Site mobilization in August 2016;
- Boxcut and portal establishment by September 2016; and
- Developed over 1km of 1:7 decline to March 2017.

165km North of Port Augusta, Pernatty Station, SA  
Project Term: 36 months | Employees: 120

### CONTRACT TYPE

- Schedule of Rates.

### KEY PLANT & EQUIPMENT

- 2 x Jumbo – Sandvik 920i Jumbo and Sandvik DD421-60C - TFX10/16;
- 1 x Charger - Normet Charmec MC605;
- 2 x Loaders – 2 x Sandvik LH621;
- 2 x Trucks – 2 x Sandvik 663;
- 1 x Service - Volvo L120F IT and Volvo L90E IT;
- 1x Grader - Cat 12H; and
- 1x Shotcrete - Jacon Maxijet Shotcreter and Normet Utimec LF600 AGI.

### KEY MILESTONES

- Commenced on site on the 23rd of August;
- First Cut in portal on the 30th of September; and
- Currently mining twin decline mine access.