



PROJECT FACT SHEET

DEEP SOUTH

SCOPE

- Mine Development, Production, Production drilling, Raise boring, Cable bolting and Narrow Vein Sub Level Stopping;
- We supplied labour, plant and material to establish greenfield underground site including site establishment, portal development, underground development and production; and
- The mine will access the orebody from the existing open pit using typical jumbo decline development and recover ore using traditional longhole open stoping methods.

KEY PROJECT OUTCOMES

- Ongoing Contract; and
- First portal cut fired on 23 October 2015.

170km North East of Kalgoorlie, WA
Project Term: 24 months | Employees: 90

PROJECT STATISTICS

- Active.

CONTRACT TYPE

- Schedule of Rates

KEY PLANT & EQUIPMENT

- 2x Jumbos - Sandvik DD420-60 and Sandvik DD421-60C - TFX10/16;
- 1x Production Drill – Atlas Copco E7C;
- 1x Charger - Normet Charmec 1610B;
- 3x Loaders - 3 x Cat R2900G - 1 Teleremote Guidance ;
- 3x Trucks – 2 x Cat AD55B, 1 x Cat AD60;
- 3x Service - Volvo L120F IT, Volvo L120E IT - Open cab and Volvo L90C IT; and
- 1x Raise bores - Atlas Copco Easer.

KEY MILESTONES

- Commenced Portal works September 2015;
- 500 metres of lateral development & 35,000 stope ore tonnes per month;
- 8.4 km of advance;
- 82,000 production drill metres;
- 350,000 t of ore mined; and
- 1,987,000 tkm's hauled.